

STEEL BUILDINGS

“Action Handling set the standard for cold rolled frames”

All our buildings are designed to BS5950, BS6399 and are supplied with a complete set of structural calculations



One of our kit buildings ready for despatch to site (see left). Each building is supplied complete down to the last nut and bolt. Each bespoke building is supplied to specification in one delivery, and can be supplied on a vehicle with its own lifting gear if off loading facilities are not available on site



Sections: pre-cut to length with holes pre-punched.
Laser cut Brackets: all holes created by accurate CAM files to ensure ease of assembly on site using 8.8 grade nuts and bolts.



Drip flashing at base as standard



The area susceptible to high winds are at the abutment of walls, all our buildings are fully braced to BS5950 using rigid bolted components

Anti-sag system as required by BS5950 (see far left)



Industrial Specification Roller shutter door c/w hand chain as standard (left).

Steel security PA Door 10 point locking system, powder coated (right)

Anti-condensation lining on all single skin roof panels

